PROP. IMPROVEMENTS

- 2,610 LF OF 12" PVC C-900 PIPE @ 0.22% SLOPE
- 140 LF OF 10" PVC C-900 PIPE (MATCH EXIST. SLOPE)
- 40 LF OF 8" PVC C-900 PIPE (MATCH EXIST. SLOPE)
- 16 NEW MANHOLES
- NEW 8-FT DIAMETER HDPE WETWELL WITH DUPLEX FLYGT GRINDER PUMPS.
- PASSIVE WETWELL VENTILATION RISER
- NEW PRECAST CONCRETE VALVE VAULT ASSEMBLY WITH DRAIN
- NEW ELECTRICAL AND CONTROL PANELS
- ABANDON EXIST. VALVE VAULT AND WETWELL

LEGEND

- 8-IN SAN — EXIST. SAN. SEWER TO BE ABANDONED
- 8-IN SAN — EXIST. SAN. SEWER TO REMAIN
- EXIST. MANHOLE
- PROP. SAN. SEWER
- PROP. MANHOLE
- CITY SANITARY SEWER BASIN 2
- CITY SANITARY SEWER BASIN 6
- PROPOSED DEVELOPMENT SITE

Sunshine811

Call 811 or visit sunshine811.com two full business days before digging to have buried facilities located and marked.

Check positive response codes before you dig!

No.	REVISIONS	DATE	BY
1-3	CONSTRUCTION COORDINATION	5/2/2023	MG

Kimley»Horn

© 2022 KIMLEY-HORN AND ASSOCIATES, INC.

2 ALHAMBRA PLAZA, SUITE 500, CORAL GABLES, FL 33134
PHONE: 786-347-2056
WWW.KIMLEY-HORN.COM REGISTRY 35106

KHA PROJECT 043904010
DATE MAY, 2023
SCALE AS SHOWN
DESIGNED BY KEG
DRAWN BY CDT
CHECKED BY SNR

SANITARY SEWER BASIN EXHIBIT

ALEXAN CRAFTS SEWER EXTENSION

CORAL GABLES FL

SHEET NUMBER
EX-1

Plotted By: Turner, Cori Sheet Set: ALEXAN CRAFTS SEWER EXTENSION Layout: SANITARY SEWER BASIN May 17, 2023 06:01:18pm K:\MIB_Civil\043904007 - Alexan Crafts (Coral Gables)\CIVIL\CADD\Exhibits\OFFSITE\043904007- Offsite-Exhibit.dwg
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.